

GPS #: 1264

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/C-7

City / Location: Newport Beach

Scale Factor: 0.99996646

Ellipsoid Red. Factor: 1.00000500

Combination Factor: 0.99997149

Convergence Angle: -00 54 12.51936

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 08.06413	117 53 38.86319	2172769.978	6061155.948	-105.036
2007.00	33 37 08.08054	117 53 38.88028	2172771.66	6061154.53	

References: CR 0933

Description:

FD 16 PENNY NAIL WITH 1 1/4" OCS BRASS TAG STAMPED "GPS 1264 1-95" FLUSH IN WOODEN DECK OF GAZEBO WALKWAY, LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND BAYSIDE DR., PROCEED NE'LY TO BAYSIDE VILLAGE TRAILER PARK. TURN LEFT AND CONTINUE ALONG TO THE "CLUB HOUSE" AND CONTACT MAIN DECK FOR A "GATE CARD". RETURN BACK TO BAYSIDE DR., TURN LEFT AND CONTINUE THROUGH GATE AND TAKE THE FIRST LEFT INTO THE MARINA PARKING LOT. TURN RIGHT, AND CONTINUE TO THE END OF THE PARKING LOT. THE MONUMENT IS LOCATED NEAR THE CENTER OF A WOODEN GAZEBO WITH WOODEN WALKWAYS LEADING TO DOCKS "J" AND "I", IN UPPER NEWPORT BAY MARINA.

