

GPS #: 1265

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/C-6

City / Location: Newport Beach

Scale Factor: 0.99996651

Ellipsoid Red. Factor: 1.00000510

Combination Factor: 0.99997163

Convergence Angle: -00 54 06.78613

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 10.02152	117 53 28.42999	2172953.904	6062041.242	-107.047
2007.00	33 37 10.03797	117 53 28.44700	2172955.59	6062039.83	

References: CR 0934

Description:

FD LEAD AND TACK WITH 1 1/4" OCS BRASS TAG STAMPED "GPS 1265 1-95" FLUSH IN CONC. SIDEWALK, LOCATED FROM THE INTER OF JAMBOREE RD. AND BACK BAY DR., PROCEED NW'LY TO A PRIVATE RD. (MAIN ENTRANCE TO MARINA) TURN LEFT AND CONTINUE TO THE GUARDED/GATED ENTRANCE. CONTINUE THROUGH AND TAKE THE FIRST RIGHT INTO THE PARKING LOT AND TRAVEL S'LY PAST THE BOAT LAUNCHING AREA. PARK NEAR THE BACK BAY CAFE. THE MONUMENT IS LOCATED IN THE CONC. SIDEWALK IN FRONT OF SAID CAFE, IN UPPER NEWPORT BAY MARINA.

