

GPS #: 1266

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/C-6

City / Location: Newport Beach

Scale Factor: 0.99996651

Ellipsoid Red. Factor: 1.00000310

Combination Factor: 0.99996964

Convergence Angle: -00 54 09.20970

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 09.91500	117 53 32.84036	2172949.011	6061668.156	-65.495
2007.00	33 37 09.93138	117 53 32.85742	2172950.69	6061666.74	

References: CR 0935

Description:

FD 2" I.P. WITH 3/4" BRASS TAG AND BRASS NAIL, UP 0.1', LOCATED FROM THE INTER OF JAMBOREE RD. AND BACK BAY DR., PROCEED NW'LY TO A PRIVATE RD. (MAIN ENTRANCE TO MARINA). TURN LEFT AND CONTINUE THROUGH THE GUARDED/GATED ENTRANCE, PROCEED TO THE FIRST RIGHT INTO THE PARKING LOT. TRAVEL SOUTH TO THE BOAT LAUNCHING AREA, PARK VEHICLE. THE MONUMENT IS REACHED BY HIKING TO THE TOP OF "CONEY ISLAND", IN UPPER NEWPORT BAY MARINA.

