

**GPS #:** 1267

**Date Destroyed:** 7/25/2000

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** 5LA

**Page/Grid:** 889/C-6

**City / Location:** Newport Beach

**Scale Factor:** 0.99996663

**Ellipsoid Red. Factor:** 1.00000470

**Combination Factor:** 0.99997142

**Convergence Angle:** -00 54 09.37063

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 14.76457	117 53 33.13320	2173439.529	6061651.116	-100.275
2007.00	33 37 14.78097	117 53 33.15027	2173441.21	6061649.70	

**References:** CR 0936

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2 1/2" I.P. WITH 1 1/4" OCS BRASS WASHER STAMPED "GPS 1267 1-95" WITH BRASS NAIL UP 0.1', LOCATED FROM THE INTER OF JAMBOREE RD. AND BACK BAY DR., PROCEED N'LY ALONG BACK BAY DR. TO SHELLMAKER RD., TURN LEFT AND CONTINUE W'LY TO A GATE/FENCE, GO THROUGH, NOW A DIRT AREA, AND CONTINUE TO A DEBRIS FENCE. TURN LEFT AND CONTINUE S'LY AND PARK BETWEEN THE U.C.I. CREW BLDG. ON LEFT AND COUNTY STORAGE BLDG. ON THE RIGHT. PROCEED ON FOOT NW'LY 220'+/- TO SAID MONUMENT LOCATED NEAR THE OSPREY NESTING AREA AND 95' S'LY OF A POWER POLE (NO NUMBER), IN UPPER NEWPORT BAY MARINA.