

GPS #: 1269

Date Destroyed:

Date Revised: 7/15/2004

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/B-5

City / Location: Unin., Orange County

Scale Factor: 0.99997745

Ellipsoid Red. Factor: 0.99998041

Combination Factor: 0.99995787

Convergence Angle: -00 49 12.19895

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 32.89834	117 44 32.34671	2210969.956	6107923.871	409.202
2007.00	33 43 32.91480	117 44 32.36264	2210971.64	6107922.55	

References: RSB 139/12-14, CR 0940

Description:

(FOUND 7/15/04 IN CACTUS PATCH) - FD 4" ALUMINUM OCS DISK STAMPED "IRV 107" IN CONC. COLLAR, UP 0.3' LOCATED FROM THE INTER OF IRVINE BLVD. AND CULVER DR., PROCEED NE'LY ALONG CULVER DR. 1 MILE TO A LOCKED METAL GATE (PRESENTLY WHITE) WITH DA-1 LOCK. CONTINUE ON CROSSING RATTLESNAKE CANYON DRAINAGE DITCH, TURN RIGHT AND CONTINUE E'LY ALONG A DIRT RD. THAT PARALLELS SAID DRAINAGE DITCH. CONTINUE 0.6 MILE TO A FORK IN THE RD. TURN LEFT AND CONTINUE 0.2 MILE TO A FOUR WAY INTER. TURN RIGHT 0.1 MILE TO A FORK IN THE RD. GO LEFT 0.1 MILE TO ANOTHER FOUR WAY INTER, GO RIGHT 0.1 MILE, THEN TAKE CENTER RD. UP HILL TO A CONC. DRAINAGE DITCH. CONTINUE 0.6 MILE TO A BRIDGE ON THE LEFT, CROSS THE DRAINAGE DITCH AND TAKE A HAIRPIN TURN TO THE LEFT AND CONTINUE 0.15 MILE. TURN RIGHT AND CONTINUE 0.1 MILE. TURN LEFT AND PROCEED 0.1 MILE TO THE MONUMENT.

