

GPS #: **1271**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/B-7

City / Location: Unin., Orange County

Scale Factor: 0.99997645

Ellipsoid Red. Factor: 0.99998928

Combination Factor: 0.99996574

Convergence Angle: -00 49 09.91686

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 02.33382	117 44 28.19382	2207875.750	6108230.413	223.969
2007.00	33 43 02.35025	117 44 28.20977	2207877.43	6108229.09	

References: RSB 125/5-9, CR 0942

Description:

FD 2 1/2" OCS BRASS CAP STAMPED "FC186 88AO" SET IN CONC., UP 0.4', LOCATED FROM THE INTER OF IRVINE BLVD. AND JEFFREY RD., PROCEED 0.55 MILE NW'LY ALONG JEFFREY RD. TO THE GUARDED ENTRANCE OF HINES NURSERIES. CONTINUE ALONG DIRT RD. 0.1 MILE AND TURN RIGHT, THEN LEFT, AND CONTINUE 0.2 MILE TURN LEFT ALONG FENCE FOR 0.4 MILE. THE MONUMENT IS LOCATED UP THE SLOPE NEXT TO A "V" DITCH.

