

GPS #: 1272

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/J-5

City / Location: Unin., Orange County

Scale Factor: 0.99997827

Ellipsoid Red. Factor: 0.99999419

Combination Factor: 0.99997246

Convergence Angle: -00 49 46.73953

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 57.29476	117 45 35.20291	2213512.154	6102651.178	121.394
2007.00	33 43 57.31094	117 45 35.21904	2213513.81	6102649.84	

References: RSB 139/12-14, CR 0938

Description:

FD 2" I.P. WITH 3/4" BRASS TAG STAMPED "LS 5831", LOCATED FROM THE INTER OF CULVER DR. AND IRVINE BLVD., PROCEED NW'LY ALONG CULVER DR. 1 MILE TO THE MONUMENT. (AREA IS CURRENTLY UNDER CONSTRUCTION).

