

GPS #: **1336**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/A-1

City / Location: Unin., Orange County

Scale Factor: 0.99999612

Ellipsoid Red. Factor: 0.99991471

Combination Factor: 0.99991084

Convergence Angle: -00 46 50.44763

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 34.54450	117 40 14.39078	2259347.580	6130372.531	1782.241
2007.00	33 51 34.56113	117 40 14.40720	2259349.28	6130371.17	

References: CR 1243

Description:

FD 2" I.P. WITH 2 1/2" BRASS CAP STAMPED "T3S R8W 1/4 S36/S1 T4S 1990 LS 5346" SET IN 3' DIA. ROCK PILE UP 0.8', LOCATED ALONG THE ORANGE/RIVERSIDE COUNTY LINE, IN THE CLEVELAND NATIONAL FOREST IN A S'LY DIRECTION FROM THE 91 FREEWAY.

