

GPS #: **1338**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997544

Ellipsoid Red. Factor: 0.99994198

Combination Factor: 0.99991742

Convergence Angle: -00 45 56.93744

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 30.60156	117 38 37.01412	2204258.148	6137848.877	1212.544
2007.00	33 42 30.61812	117 38 37.02998	2204259.84	6137847.56	

References: CR 1295

Description:

FD 2" I.P. WITH BRASS NAIL AND 1 1/2" OCS BRASS TAG STAMPED "GPS 1338 5-95" UP 0.1' IN DIRT SHOULDER LOCATED 5' +/- W'LY FROM THE W'LY A.C. CURB ALONG SANTIAGO CANYON RD., 0.65 MILE S'LY FROM MODJESKA CANYON RD. AND 0.25 MILE N'LY FROM GERTNER ESTATE RD.

