

GPS #: **1339**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997530

Ellipsoid Red. Factor: 0.99994083

Combination Factor: 0.99991613

Convergence Angle: -00 45 55.27169

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 26.07843	117 38 33.98283	2203797.564	6138098.826	1236.533
2007.00	33 42 26.09492	117 38 33.99868	2203799.25	6138097.51	

References: CR 1298

Description:

FD 2" I.P. WITH BRASS NAIL AND 1 1/2" OCS BRASS TAG STAMPED "GPS 1339 5-95" UP 0.1' IN DIRT SHOULDER LOCATED 10' +/- W'LY FROM THE W'LY A.C. CURB ALONG SANTIAGO CANYON RD., 15' +/- NW'LY FROM A DOWN DRAIN, 0.75 MILE S'LY FROM MODJESKA CANYON RD. AND 0.25 MILE N'LY FROM GERTNER ESTATE RD.

