

GPS #: **1340**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997536

Ellipsoid Red. Factor: 0.99993746

Combination Factor: 0.99991282

Convergence Angle: -00 45 51.73624

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 27.93679	117 38 27.54908	2203978.137	6138644.805	1307.002
2007.00	33 42 27.95336	117 38 27.56504	2203979.83	6138643.48	

References: CR 1297

Description:

FD 2" I.P. WITH BRASS NAIL AND 1 1/2" OCS BRASS TAG STAMPED "GPS 1340 5-95" UP 0.1' IN DIRT SHOULDER LOCATED 8' +/- N'LY FROM N'LY EDGE OF PAVEMENT OF MODJESKA GRADE RD., E'LY FROM THE CANYON HEIGHTS DR.WAY.

