

GPS #: **1344**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3UU-4-92

OCS Index Map: 5LB

Page/Grid: 862/E-1

City / Location: Unin., Orange County

Scale Factor: 0.99997534

Ellipsoid Red. Factor: 0.99993732

Combination Factor: 0.99991266

Convergence Angle: -00 45 51.83866

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 27.30415	117 38 27.73547	2203914.405	6138628.208	1309.925
2007.00	33 42 27.32074	117 38 27.75134	2203916.10	6138626.89	

References: CR 1292

Description:

FD 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3UU-4-92" SET IN 5" X 5" CONC. POST UP 0.2' LOCATED AT THE SW'LY CORNER OF CANYON HEIGHTS DR. AND MODJESKA GRADE RD., 35' W'LY OF THE CENTERLINE OF MODJESKA GRADE RD., AT THE UPHILL CURVE OF THE HORSESHOE, 1' WEST OF THE W'LY UPHILL BARRICADE, 1' ABOVE RD. GRADE.

