

GPS #: 1347

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/B-6

City / Location: Unin., Orange County

Scale Factor: 0.99998343

Ellipsoid Red. Factor: 0.99993666

Combination Factor: 0.99992010

Convergence Angle: -00 46 42.62942

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 23.21064	117 40 00.16338	2227863.218	6131144.648	1323.524
2007.00	33 46 23.22709	117 40 00.17939	2227864.90	6131143.32	

References: CR 1271

Description:

FD 2" I.P. WITH 3 1/4" USDA FOREST SERVICE DISK STAMPED "RLS COR 2, T4S, R8W, S36, S1, T5S, R8W, 1982" UP 0.2' IN DIRT. LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG SILVERADO CANYON RD. 0.1 MILE TO A "T" INTER WITH BLACKSTAR CANYON RD. ON LEFT. TURN LEFT AND PROCEED NW'LY ALONG BLACKSTAR CANYON RD. 0.75 MILES TO AN A.C. RD. ON RIGHT KNOWN AS "BAKER CANYON RD.". TURN RIGHT ON SAID RD. HEADING N'LY 0.35 MILES TO A LOCKED BARBED WIRE GATE (DA1) ON LEFT. PROCEED THROUGH GATE AND ALONG DIRT RD. N'LY 100' +/- TO A "Y" IN THE RD. BEAR LEFT, NW'LY ALONG DIRT RD., ACROSS CREEK BED AND WINDING UPHILL 1.2 MILES TO A BARBED WIRE GATE. PROCEED THROUGH GATE AND CONTINUE ALONG DIRT RD. 0.1 MILE TO THE FIRST "Y" TO THE RIGHT IN RD. BEAR RIGHT AND CONTINUE 0.1 MILE TO THE STEEL POWER LINE TOWER. PARK HERE. MONUMENT IS LOCATED 150' +/- E'LY OF SAID TOWER AND 70' +/- E'LY OF A 5" X 8" WOOD POST FOREST SERVICE MONUMENT. WITNESS PADDLE IS SET 3' W'LY FROM MONUMENT.

