

GPS #: 1361

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 954/C-2

City / Location: Unin., Orange County

Scale Factor: 0.99996092

Ellipsoid Red. Factor: 0.99993871

Combination Factor: 0.99989964

Convergence Angle: -00 41 33.12227

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 42.92740	117 30 36.92907	2144344.904	6177684.542	1280.700
2007.00	33 32 42.94431	117 30 36.94483	2144346.63	6177683.23	

References: CR 1403

Description:

FD 2" I.P. BENT OVER N'LY WITH A BRASS STEM IN CONC. IN TOP OF PIPE - 3.0' EXPOSED. (HELD CENTER OF PIPE AT THE GROUND) LOCATED FROM THE INTER OF ORTEGA HWY., AND VERDUGO CANYON RD., PROCEED NE'LY AND S'LY ALONG VERDUGO CANYON RD. 4.4 MILES TO A FOOT PATH ON THE RIGHT (W'LY). PROCEED ALONG SAID FOOT PATH W'LY 1200' +/- PAST VACANT BUILDING TO SAID MONUMENT LOCATED ALONG THE RANCHO MISSION VIEJO LINE.

