

GPS #: 1363

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 954/G-1

City / Location: Unin., Orange County

Scale Factor: 0.99996118

Ellipsoid Red. Factor: 0.99996142

Combination Factor: 0.99992260

Convergence Angle: -00 41 33.34583

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 57.23533	117 30 37.33591	2145791.416	6177667.593	806.173
2007.00	33 32 57.25222	117 30 37.35167	2145793.14	6177666.28	

References: CR 1405

Description:

FD 9" X 12" X 22" STONE - UP 1.0' WITH CHISELED GROOVES AS FOLLOWS: "MV" ON W'LY FACE WITH 3 GROOVES ON THE NORTH AND SOUTH FACE, AND "TCFR CC" ON EAST FACE WITH A PUNCH MARK IN A CHISELED "+" ON TOP OF ROCK. LOCATED FROM THE INTER OF ORTEGA HWY. AND VERDUGO CANYON RD., PROCEED NE'LY ALONG VERDUGO CANYON RD. 3 MILES +/- TO THE RANCHO MISSION VIEJO LINE. MONUMENT IS LOCATED 700' +/- S'LY ALONG SAID MISSION VIEJO LINE.

