

GPS #: **1364**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 924/C-7

City / Location: Unin., Orange County

Scale Factor: 0.99996159

Ellipsoid Red. Factor: 0.99994142

Combination Factor: 0.99990301

Convergence Angle: -00 41 33.41304

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 19.65886	117 30 37.45822	2148057.880	6177684.640	1224.095
2007.00	33 33 19.67581	117 30 37.47395	2148059.61	6177683.33	

References: CR 1406

Description:

FD 2" I.P. WITH A 2 1/2" CAP STAMPED "RMV LINE RE 4231 RE 2839", UP 1.3' SET IN 3.0' DIA. ROCK MOUND. LOCATED FROM THE INTER OF ORTEGA HWY. AND CARRILLO RANCH RD., PROCEED NE'LY ALONG SAID RD. 3.3 MILES TO A HAIRPIN CURVE. PARK HERE. HIKE ALONG RIDGE 1400' +/- SW'LY TO SAID MONUMENT.

