

**GPS #:** **1366**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 924/C-7

City / Location: Unin., Orange County

Scale Factor: 0.99996181

Ellipsoid Red. Factor: 0.99994097

Combination Factor: 0.99990279

Convergence Angle: -00 41 33.14926

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 31.63835	117 30 36.97818	2149268.153	6177739.896	1233.528
2007.00	33 33 31.65527	117 30 36.99387	2149269.88	6177738.59	

References: CR 1408

**Description:**

FD 2" I.P. WITH NAIL & TAG STAMPED "LS 2609" IN CONC., SET IN 2' DIA., 1.5' HIGH ROCK MOUND. LOCATED FROM THE INTER OF ORTEGA HWY. AND CARRILLO RANCH RD., PROCEED NE'LY ALONG SAID RD. 3.0 MILES +/- SAID MONUMENT IS LOCATED 25' +/- S'LY OF EDGE OF PAVEMENT AND 50' +/- E'LY FROM THE MISSION VIEJO FENCE.

