

GPS #: **1367**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 924/C-6

City / Location: Unin., Orange County

Scale Factor: 0.99996215

Ellipsoid Red. Factor: 0.99995968

Combination Factor: 0.99992183

Convergence Angle: -00 41 33.65644

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

No PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 49.05425	117 30 37.90114	2151029.320	6177683.079	842.672
2007.00	33 33 49.07120	117 30 37.91686	2151031.05	6177681.77	

References: CR 1409

Description:

FD 2" I.P. WITH A 2 1/2" BRASS CAP STAMPED "RMV S16 S9 CC RE 4231 RE 2839", UP 2.0', SET IN A 3' DIA. ROCK PILE. LOCATED FROM THE INTER OF ORTEGA HWY. AND LUCAS CANYON RD. PROCEED NE'LY ALONG SAID RD. 2.1 MILES, PARK HERE. HIKE 2000' +/- E'LY TO SAID MONUMENT.

