

**GPS #:** 1368

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 924/C-4

City / Location: Unin., Orange County

Scale Factor: 0.99996299

Ellipsoid Red. Factor: 0.99992962

Combination Factor: 0.99989262

Convergence Angle: -00 41 33.98363

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 31.63144	117 30 38.49655	2155333.208	6177684.734	1470.673
2007.00	33 34 31.64831	117 30 38.51221	2155334.93	6177683.43	

References: CR 1410

**Description:**

FD 2" I.P. WITH 2 1/4" BRASS CAP STAMPED "LS 3914 EAST LINE RMV", DOWN 0.3'. LOCATED FROM THE INTER OF ORTEGA HWY. AND LUCAS CANYON RD. PROCEED NE'LY ALONG SAID RD. 2.0 MILES +/- TO A FIRE BREAK ON THE LEFT. PROCEED ALONG SAID FIREBREAK 1.9 MILES +/- N'LY TO SAID MONUMENT LOCATED ALONG RANCHO MISSION VIEJO LINE.

