

GPS #: **1370**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 865/D-7

City / Location: Unin., Orange County

Scale Factor: 0.99996990

Ellipsoid Red. Factor: 0.99986604

Combination Factor: 0.99983595

Convergence Angle: -00 38 24.75926

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 22.08599	117 24 54.15022	2184351.212	6207145.119	2799.368
2007.00	33 39 22.10313	117 24 54.16570	2184352.96	6207143.83	

References: RSB 160/17-32

Description:

FD 2" ALUMINUM DISK STAMPED "DEPT. OF AGRICULTURE FOREST SERVICE T6S R5W S8 S9 S17 S16 LS 4550". LOCATED FROM THE INTER OF ORTEGA HWY. AND MAIN DIVIDE RD. (FOREST SERVICE 3504), WHICH IS LOCATED 0.3 MILES E'LY FROM THE EL CARISO RANGER STATION, PROCEED 0.6 MILES +/- TO SAID MONUMENT LOCATED 200' +/- S'LY FROM SAID RD.

