

GPS #: **1373**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 865/D-7

City / Location: Unin., Orange County

Scale Factor: 0.99997028

Ellipsoid Red. Factor: 0.99986511

Combination Factor: 0.99983539

Convergence Angle: -00 38 22.11997

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 35.82939	117 24 49.34728	2185735.770	6207566.587	2818.784
2007.00	33 39 35.84645	117 24 49.36275	2185737.51	6207565.30	

References: RSB 160/17-32, CR 1401

Description:

FD 1" I.P., EMPTY, DOWN 0.1'. LOCATED FROM THE INTER OF ORTEGA HWY. AND MAIN DIVIDE RD. (FOREST SERVICE 3504), WHICH IS LOCATED 0.3 MILES E'LY FROM THE EL CARISO RANGER STATION, PROCEED 1.0 MILE +/- TO SAID MONUMENT LOCATED 30' +/- E'LY FROM SAID RD.

