

GPS #: **1374**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 865/D-6

City / Location: Unin., Orange County

Scale Factor: 0.99997037

Ellipsoid Red. Factor: 0.99985994

Combination Factor: 0.99983032

Convergence Angle: -00 38 24.77544

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 39.25239	117 24 54.17966	2186086.306	6207162.019	2926.766
2007.00	33 39 39.26950	117 24 54.19514	2186088.05	6207160.73	

References: RSB 160/17-32, CR 1401

Description:

FD 1" I.P. WITH A 3/4" BRASS TAG STAMPED "LS3698", FLUSH LOCATED FROM THE INTER OF ORTEGA HWY. AND MAIN DIVIDE RD. (FOREST SERVICE 3504), WHICH IS LOCATED 0.3 MILES E'LY FROM THE EL CARISO RANGER STATION, PROCEED 1.0 MILE +/- TO SAID MONUMENT LOCATED ON S'LY SLOPE OF HILL E'LY FROM SAID RD.

