

GPS #: **1378**

Date Destroyed: **6/29/2000**
Date Revised: **4/23/1996**
Benchmark Designation: **3T-9-92**
OCS Index Map: **5LA**
Page/Grid: **890/B-6**
City / Location: **Unin., Orange County**

Scale Factor: **0.99996658**
Ellipsoid Red. Factor: **0.99998259**
Combination Factor: **0.99994917**
Convergence Angle: **-00 51 58.63057**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 12.56769	117 49 35.21532	2172906.939	6081764.570	365.793
2007.00	33 37 12.58420	117 49 35.23207	2172908.63	6081763.18	

References: OCS FILE # IW94/5-51N, GEODETIC UNIT

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 1/4" ALUMINUM OCS BENCHMARK CAP STAMPED "3T-9-92", LOCATED 0.9 MILE N'LY ALONG NEWPORT COAST DR. FROM SAN JOAQUIN HILLS RD. TO A CATCH BASIN ON THE E'LY SIDE OF NEWPORT COAST DR., SET AT THE SW CORNER OF A 4' X 15' CATCH BASIN, 53' E'LY OF THE CENTERLINE OF NEWPORT COAST DR.