

**GPS #:** **1379**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/B-7

City / Location: Unin., Orange County

Scale Factor: 0.99996576

Ellipsoid Red. Factor: 0.99997631

Combination Factor: 0.99994208

Convergence Angle: -00 51 57.09912

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 38.32668	117 49 32.42842	2169442.740	6081947.914	497.033
2007.00	33 36 38.34318	117 49 32.44556	2169444.43	6081946.49	

References: RSB 159/23

**Description:**

FD LEAD & TAG STAMPED "LS 4965" FLUSH IN CONC., LOCATED ON THE N'LY END OF A MEDIAN, AT THE CENTERLINE EC ALONG NEWPORT COAST DR., 0.6' S'LY FROM EDGE OF CONC. NOSE. (ALSO KNOWN AS GPS # 2586)

