

GPS #: 1412

Date Destroyed:

Date Revised: 6/9/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-6

City / Location: Unin., Orange County

Scale Factor: 0.99995936

Ellipsoid Red. Factor: 0.99999736

Combination Factor: 0.99995671

Convergence Angle: -00 45 13.59358

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 09.42726	117 37 18.13705	2135323.621	6143605.934	55.056
2007.00	33 31 09.44419	117 37 18.15283	2135325.35	6143604.62	

References: RSB 154/8-18

Description:

FD 2 1/2" I.P. WITH 2" BRASS CAP STAMPED "GPS 1412 9-95" FLUSH IN GRASS, LOCATED 0.1 MILE W'LY FROM THE INTER OF ORTEGA HWY. AND LA PATA AVE., 50' +/- S'LY OF THE CENTERLINE OF ORTEGA HWY., 10' +/- S'LY FROM A CHAIN LINK FENCE, 60' +/- E'LY FROM AN ANGLE POINT IN THE CHAIN LINK FENCE.

