

**GPS #:** **1413**

**Date Destroyed:** **2/10/1998**

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** **6LB**

**Page/Grid:** **952/J-5**

**City / Location:** **Unin., Orange County**

**Scale Factor:** **0.99995949**

**Ellipsoid Red. Factor:** **0.99999180**

**Combination Factor:** **0.99995129**

**Convergence Angle:** **-00 44 58.73131**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 17.91303	117 36 51.09188	2136151.218	6145906.657	171.269
2007.00	33 31 17.92989	117 36 51.10759	2136152.94	6145905.35	

**References:** **RSB 154/8-18**

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH 1 1/2" BRASS OCS TAG STAMPED "GPS 1413 9-95" UP 0.3' IN DIRT. LOCATED FROM THE INTER OF ORTEGA HWY. AND LA PATA AVE., PROCEED 0.35 MILES E'LY ALONG ORTEGA HWY. MONUMENT IS LOCATED BY THE APPARENT B.C., N'LY OF THE HWY., 4' N'LY FROM THE EDGE OF PAVEMENT.