

GPS #: **1433**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-6

City / Location: Unin., Orange County

Scale Factor: 0.99995912

Ellipsoid Red. Factor: 0.99999740

Combination Factor: 0.99995652

Convergence Angle: -00 45 17.21757

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 54.08424	117 37 24.73277	2133780.291	6143027.145	54.268
2007.00	33 30 54.10106	117 37 24.74858	2133782.01	6143025.83	

References: RSB 154/8-18

Description:

FD 2 1/2" I.P. WITH 2" BRASS CAP STAMPED "GPS 1433 9-95" FLUSH. LOCATED SOUTH ON LA PATA AVE., 0.7 MILES FROM ITS INTER WITH ORTEGA HWY., 300' +/- NORTH OF THE RD., IN A FIELD.

