

GPS #: **1434**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-6

City / Location: Unin., Orange County

Scale Factor: 0.99995926

Ellipsoid Red. Factor: 0.99999609

Combination Factor: 0.99995535

Convergence Angle: -00 45 10.32800

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 03.32715	117 37 12.19529	2134700.484	6144100.829	81.791
2007.00	33 31 03.34405	117 37 12.21115	2134702.21	6144099.51	

References: RSB 154/8-18

Description:

FD PUNCHED SPIKE WITH 1 1/2" OCS BRASS TAG
STAMPED "GPS 1434 9-95", FLUSH. LOCATED ON LA
PATA AVE. 0.15 MILES SOUTH OF ORTEGA HWY., ON
THE NORTH SIDE OF THE RD.

