

GPS #: 1448

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/G-1

City / Location: Unin., Orange County

Scale Factor: 0.99996128

Ellipsoid Red. Factor: 0.99997383

Combination Factor: 0.99993511

Convergence Angle: -00 45 21.08686

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 02.73716	117 37 31.77402	2146790.819	6142602.585	546.889
2007.00	33 33 02.75400	117 37 31.78995	2146792.54	6142601.26	

References: RSB 154/8-18

Description:

FD 2" I.P. WITH 1 3/4" OCS BRASS CAP STAMPED
"1448 9-95" FLUSH. SET AT THE PI OF THE FENCE
LINE. (NO TO REACH DESCRIPTION. AREA UNDER
DEVELOPMENT)

