

GPS #: 1449

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: M-567
OCS Index Map: 6LB
Page/Grid: 923/C-7
City / Location: Unin., Orange County

Scale Factor: 0.99996188
Ellipsoid Red. Factor: 0.99998504
Combination Factor: 0.99994692
Convergence Angle: -00 44 03.11510

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 35.12303	117 35 09.88272	2149907.876	6154651.994	312.700
2007.00	33 33 35.14001	117 35 09.89840	2149909.61	6154650.69	

References: RSB 154/8-18

Description:

FD 3 3/4" USC&GS BRASS DISK STAMPED "M-567 1939" LOCATED FROM THE SAN DIEGO FREEWAY (INTERSTATE 5) GO NE ON ORTEGA HWY. (STATE HWY. 74) 5.3 MILES TO A PAVED RD. ON LEFT, GO 0.4 MILE N'LY ON PAVED RD. TO A FORK, KEEP RIGHT AND GO 0.2 MILE FARTHER NORTH TO A DIRT RD. ON LEFT, GO LEFT 0.8 MILE W'LY, AS IT FOLLOWS AROUND THE BASE OF THE HILL, TO A DIRT RD. ON RIGHT, GO RIGHT 1.65 MILES N'LY UP GOBERNADORA CANYON TO A METAL GATE, CONTINUE ON N'LY PAST GATE 1.3 MILES ON DIRT RD. TO ANOTHER METAL GATE, AND WIND MILL ON LEFT, 287' EAST OF THE EAST GATE POST OF STEEL GATE, 1' SOUTH OF THE BARBED WIRE FENCE, 273' NE OF CENTER OF WINDMILL, 38' EAST OF POST AT FORMER GATE LOCATION, 28' EAST OF ANGLE POINT IN FENCE AT FORMER GATE LOCATION, 0.8' SOUTH OF A STEEL POST AND PADDLE BOARD.

