

GPS #: 1451

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: 3EE-25-92
OCS Index Map: 6LA
Page/Grid: 922/E-3
City / Location: Unin., Orange County

Scale Factor: 0.99996397
Ellipsoid Red. Factor: 0.99997563
Combination Factor: 0.99993960
Convergence Angle: -00 45 56.22426

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 35 18.09286 | 117 38 35.71628 | 2160542.855 | 6137374.343 | 509.238 |
| 2007.00 | 33 35 18.10974 | 117 38 35.73220 | 2160544.58 | 6137373.02 | |

References: RSB 154/8-18

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3EE-25-92", SET IN THE NORTHEASTERLY CORNER OF A 4 FT. BY 16 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHEASTERLY CORNER OF THE INTERSECTION OF SAN RAFAEL AND OSO PARKWAY, 90 FT. SOUTHERLY OF THE CENTERLINE OF OSO AND 25 FT. EASTERLY OF THE CENTERLINE OF SAN RAFAEL. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

