

GPS #: 1452

Date Destroyed: 4/12/2016
Date Revised: 4/23/1996
Benchmark Designation:
OCS Index Map: 6LB
Page/Grid: 952/G-3
City / Location: Unin., Orange County

Scale Factor: 0.99996025
Ellipsoid Red. Factor: 0.99997041
Combination Factor: 0.99993066
Convergence Angle: -00 45 24.99278

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 04.21984	117 37 38.88193	2140884.532	6141922.946	618.362
2007.00	33 32 04.23676	117 37 38.89751	2140886.26	6141921.65	

References: RSB 154/8-18

Description:

FD 2" I.P. WITH 3 3/4" OCS ALUMINUM TRIANGULATION DISK STAMPED "7-7-29" SET IN 8" DIA. CONC. COLLAR, UP 0.2'. (NO TO REACH DESCRIPTION. AREA UNDER DEVELOPMENT.)

