

GPS #: 1453

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation:
OCS Index Map: 6LB
Page/Grid: 953/B-6
City / Location: Unin., Orange County

Scale Factor: 0.99995895
Ellipsoid Red. Factor: 0.99996675
Combination Factor: 0.99992571
Convergence Angle: -00 44 29.51594

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 43.26793	117 35 57.92640	2132591.145	6150361.933	694.835
2007.00	33 30 43.28482	117 35 57.94206	2132592.87	6150360.63	

References: RSB 154/8-18

Description:

FD 2" I.P. WITH 3 3/4" OCS ALUMINUM TRIANGULATION DISK STAMPED "8-7-3" SET IN 8" DIA. CONC. COLLAR, UP 0.2', LOCATED FROM THE INTER OF ORTEGA HWY. AND LA PATA AVE., PROCEED E'LY ALONG ORTEGA HWY. 0.5 MILES TO A DIRT RD. AND LOCKED IRON GATE (DA1) ON RIGHT, RD. KNOWN AS "RADIO TOWER RD.". PROCEED THROUGH GATE HEADING S'LY AND WINDING UPHILL 1.1 MILES AND PARK. MONUMENT IS LOCATED 350' +/- E'LY OF RD. AND ON E'LY SIDE OF SMALL KNOLL, 75' +/- NE'LY OF LARGE SCRUB OAK TREE, 15' +/- E'LY OF ANGLE POINT IN BARBED WIRE FENCE.

