

GPS #: 1458

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-7

City / Location: Unin., Orange County

Scale Factor: 0.99995877

Ellipsoid Red. Factor: 0.99998617

Combination Factor: 0.99994494

Convergence Angle: -00 45 15.99709

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 30 30.86340 | 117 37 22.51177 | 2131430.946 | 6143184.268 | 288.976 |
| 2007.00 | 33 30 30.88028 | 117 37 22.52749 | 2131432.67 | 6143182.96 | |

References: RSB 154/8-18

Description:

FD 2" IP WITH 2 1/4" OCS ALUMINUM CAP STAMPED "G-234" UP 0.1'. LOCATED FROM THE INTER OF ORTEGA HWY. AND LA PATA AVE., PROCEED S'LY ALONG LA PATA AVE. 0.9 MILES. STATION IS LOCATED THROUGH A GATE ON THE RIGHT, 200' +/- WEST OF THE RD.

