

GPS #: **1461**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-3

City / Location: Unin., Orange County

Scale Factor: 0.99996384

Ellipsoid Red. Factor: 0.99997129

Combination Factor: 0.99993513

Convergence Angle: -00 45 17.37065

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 12.14102	117 37 25.01134	2159861.949	6143347.182	600.002
2007.00	33 35 12.15797	117 37 25.02712	2159863.68	6143345.87	

References: RSB 154/8-18

Description:

FD PUNCHED SPIKE WITH ALUMINUM WASHER
STAMPED "LS 5557" FLUSH IN A.C. MEDIAN.
LOCATED ALONG THE CENTERLINE OF OSO PKWY. ,
0.5 MILES EAST OF THE INTER WITH ANTONIO
PKWY.

