

**GPS #:** **1463**

**Date Destroyed:** **3/15/1999**  
**Date Revised:** **4/23/1996**  
**Benchmark Designation:**  
**OCS Index Map:** **6LB**  
**Page/Grid:** **922/G-3**  
**City / Location:** **Unin., Orange County**

**Scale Factor:** **0.99996373**  
**Ellipsoid Red. Factor:** **0.99997347**  
**Combination Factor:** **0.99993720**  
**Convergence Angle:** **-00 45 21.36345**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 07.07748	117 37 32.27735	2159358.285	6142725.803	554.382
2007.00	33 35 07.09436	117 37 32.29314	2159360.01	6142724.49	

**References:** RSB 154/8-18

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE WITH ALUMINUM WASHER STAMPED "LS 5557" FLUSH IN A.C. MEDIAN. LOCATED AT AN EC ALONG THE CENTERLINE OF OSO PKWY. 0.3 MILES EAST OF THE INTER WITH ANTONIO PKWY. RESET WITH 2" IP AND TAG STAMPED "LS 5557". POSITION DIFFERS FROM ORIGINAL GPS POSITION BY 0.07'.