

GPS #: **1468**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/H-3

City / Location: Unin., Orange County

Scale Factor: 0.99996385

Ellipsoid Red. Factor: 0.99996886

Combination Factor: 0.99993272

Convergence Angle: -00 45 05.96631

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 12.70138	117 37 04.25798	2159895.503	6145103.439	650.648
2007.00	33 35 12.71828	117 37 04.27373	2159897.23	6145102.13	

References: RSB 154/8-18

Description:

FD PUNCHED SPIKE WITH ALUMINUM WASHER
STAMPED "LS 5557" FLUSH IN A.C. MEDIAN.
LOCATED AT AN EC ALONG THE CENTERLINE OF
OSO PKWY., 0.8 MILES EAST OF THE INTER WITH
ANTONIO PKWY.

