

GPS #: **1472**

Date Destroyed:

Date Revised: 3/5/2008

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-6

City / Location: Unin., Orange County

Scale Factor: 0.99995912

Ellipsoid Red. Factor: 0.99999475

Combination Factor: 0.99995387

Convergence Angle: -00 45 13.73821

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 54.10712	117 37 18.40112	2133775.547	6143563.206	109.606
2007.00	33 30 54.12399	117 37 18.41693	2133777.27	6143561.89	

References: RSB 154/8-18, CR 2007-2377

Description:

UNDER MOVABLE CONC. DIVIDER PER CR 2007-2377.
FD 2" BRASS DISK STAMPED "LS 7846" FD 2 1/4" OCS
ALUMINUM CAP STAMPED "6-76" DOWN 1.6" IN OCS
WELL MONUMENT. LOCATED AT AN APPARENT EC
ALONG THE CENTERLINE OF LA PATA AVE. 0.3
MILES SOUTH OF THE INTER WITH ORTEGA HWY.

