

GPS #: **1473**

Date Destroyed:

Date Revised: 3/5/2008

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-7

City / Location: Unin., Orange County

Scale Factor: 0.99995895

Ellipsoid Red. Factor: 0.99999121

Combination Factor: 0.99995016

Convergence Angle: -00 45 15.58229

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 43.16031	117 37 21.75692	2132672.920	6143264.541	183.743
2007.00	33 30 43.17715	117 37 21.77267	2132674.64	6143263.23	

References: RSB 154/8-18, CR 2007-2376

Description:

UNDER MOVABLE CONC. DIVIDER PER CR 2007-2376.
FD 2 1/4" OCS ALUMINUM CAP STAMPED "6-76"
DOWN 1.9' IN OCS WELL MONUMENT. LOCATED AT
AN APPARENT BC ALONG THE CENTERLINE OF LA
PATA AVE. 0.55 MILES SOUTH OF THE INTER WITH
ORTEGA HWY.

