

GPS #: **1474**

Date Destroyed:

Date Revised: 3/5/2008

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-7

City / Location: Unin., Orange County

Scale Factor: 0.99995880

Ellipsoid Red. Factor: 0.99998787

Combination Factor: 0.99994667

Convergence Angle: -00 45 14.81119

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 32.88019	117 37 20.35369	2131632.372	6143369.665	253.559
2007.00	33 30 32.89711	117 37 20.36938	2131634.10	6143368.36	

References: RSB 154/8-18, CR 2007-2375

Description:

UNDER MOVABLE CONC. DIVIDER PER CR 2007-2375.
FD PUNCHED ROUNDHEAD SPIKE WITH 1 1/2" OCS
BRASS WASHER DOWN 0.4'. LOCATED AT AN
APPARENT EC ALONG THE CENTERLINE OF LA
PATA AVE. 0.75 MILES SOUTH OF THE INTER WITH
ORTEGA HWY.

