

GPS #: **1476**

Date Destroyed:

Date Revised: 3/5/2008

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/H-7

City / Location: Unin., Orange County

Scale Factor: 0.99995868

Ellipsoid Red. Factor: 0.99998589

Combination Factor: 0.99994458

Convergence Angle: -00 45 13.45085

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 24.87732	117 37 17.87818	2130820.785	6143568.612	294.786
2007.00	33 30 24.89421	117 37 17.89395	2130822.51	6143567.30	

References: RSB 154/8-18, CR 2007-2374

Description:

UNDER MOVABLE CONC. DIVIDER PER CR 2007-2374.
FD PUNCHED ROUNDHEAD SPIKE WITH 1 1/2" OCS
BRASS WASHER DOWN 0.4'. LOCATED AT AN
APPARENT BC ALONG THE CENTERLINE OF LA
PATA AVE. SOUTH 1.0 MILES FROM THE INTER WITH
ORTEGA HWY.

