

GPS #: **1480**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: V-282

OCS Index Map: 6LB

Page/Grid: 1023/C-3

City / Location: San Diego Co.

Scale Factor: 0.99995456

Ellipsoid Red. Factor: 1.00000475

Combination Factor: 0.99995931

Convergence Angle: -00 44 16.95302

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 23 10.17897	117 35 35.06467	2086774.054	6151707.561	-99.363
2007.00	33 23 10.19588	117 35 35.08016	2086775.78	6151706.27	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "V-282". LOCATED 4.3 KILOMETERS (2.65 MILES) SE ALONG INTERSTATE 5 FROM THE EL CAMINO REAL OVERPASS IN SAN CLEMENTE TO THE BASILONE RD. EXIT, THENCE 0.9 OF A KILOMETER (0.55 OF A MILE) SE ALONG A FRONTAGE RD. LEADING TO THE SAN ONOFRE STATE PARK, THENCE 1.8 KILOMETERS (1.1 MILES) NW ALONG THE ATCHISON TOPEKA AND SANTA FE RAILRD., IN THE RAILRD. BRIDGE OVER THE SAN MATEO CREEK, IN TOP OF THE FIRST CONC. PIER WHICH IS NW OF THE SE END OF THE BRIDGE, 3.3 METERS (10.8') SW OF THE SW RAIL.

