

GPS #: 1485

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: LP-5-72

OCS Index Map: 6LB

Page/Grid: 972/H-1

City / Location: Unin., Orange County

Scale Factor: 0.99995847

Ellipsoid Red. Factor: 0.99998195

Combination Factor: 0.99994042

Convergence Angle: -00 45 11.47949

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 09.98202	117 37 14.29075	2129311.364	6143852.558	377.237
2007.00	33 30 09.99892	117 37 14.30658	2129313.09	6143851.24	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "LP-5-72". LOCATED FROM THE INTER OF ORTEGA HWY. AND LA PATA AVE., GO S'LY ON LA PATA AVE. 1.4 MILES TO A STEEL GATE ON THE RIGHT, GO THRU GATE AND PROCEED 0.1 MILE UP A HILL TO THE MOST W'LY OF 2 HIGH VOLTAGE TOWERS, ON LINE BETWEEN THE NE AND SE LEGS OF THE TOWER, 10' SOUTH OF THE NE LEG, 30 FT EAST OF A BARBED WIRE FENCE, SET IN TOP OF A CONC. POST, 0.5' ABOVE THE GROUND.

