

GPS #: 1486

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: 3XX-3-84
OCS Index Map: 6LA
Page/Grid: 951/G-2
City / Location: Laguna Niguel

Scale Factor: 0.99996098
Ellipsoid Red. Factor: 0.99999587
Combination Factor: 0.99995685
Convergence Angle: -00 47 54.44195

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 32 46.15032 | 117 42 10.84626 | 2145434.783 | 6118963.084 | 86.273 |
| 2007.00 | 33 32 46.16732 | 117 42 10.86230 | 2145436.52 | 6118961.75 | |

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3XX-3-84", SET IN THE SOUTHERLY END OF A 15 FT. LONG CONCRETE HEADWALL FOR A REINFORCED CONCRETE BOX CULVERT. MONUMENT IS LOCATED ALONG THE WESTERLY SIDE OF LA PAZ ROAD, 0.3 MILES SOUTHERLY ALONG LA PAZ FROM THE CENTERLINE OF YOSEMITE ROAD AND 70 FT. WESTERLY OF THE CENTERLINE OF LA PAZ. MONUMENT IS SET 19 FT. BELOW THE SURFACE OF LA PAZ ROAD.

