

GPS #: **1488**

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: 3EE-22-91
OCS Index Map: 6LA
Page/Grid: 922/E-3
City / Location: Mission Viejo

Scale Factor: 0.99996401
Ellipsoid Red. Factor: 0.99997655
Combination Factor: 0.99994056
Convergence Angle: -00 46 00.88422

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 20.09357	117 38 44.19639	2160754.659	6136659.739	489.979
2007.00	33 35 20.11042	117 38 44.21226	2160756.38	6136658.42	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "3EE-22-91". LOCATED AT THE NORTH W'LY PART OF THE INTER OF FELIPE RD. AND OSO PKWY., 86' N'LY OF CENTERLINE OF OSO PKWY., 18' W'LY OF PAINTED CENTERLINE OF FELIPE RD., SET AT THE NORTH E'LY CORNER OF A 6' X 4' CATCH BASIN, 1' BEHIND CURB FACE.

