

GPS #: 1489

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3EE-14-72

OCS Index Map: 6LB

Page/Grid: 923/A-2

City / Location: Unin., Orange County

Scale Factor: 0.99996466

Ellipsoid Red. Factor: 0.99996464

Combination Factor: 0.99992930

Convergence Angle: -00 44 30.87126

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 49.83791	117 36 00.39279	2163578.458	6150554.359	739.037
2007.00	33 35 49.85487	117 36 00.40864	2163580.19	6150553.04	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 1995 - 1.5 MILES EASTERLY OF THE EAST END OF THE OSO BRIDGE OVER TRABUCO CREEK TO A LOCKED GATE ON THE NORTHERLY SIDE OF OSO PARKWAY, PROCEED THROUGH THE GATE AND TRAVEL ALONG ROAD FOR 0.3 MILES TO A SECOND LOCKED GATE, PROCEED THROUGH GATE AND TRAVEL ON SAID DIRT ROAD TO A FORK IN ROAD NEAR OLD WATER TANK ON THE WESTERLY SIDE OF THE ROAD, TAKE ROAD BEARING RIGHT AND PROCEED 0.4 MILES EASTERLY TO EARTHEN DAM AND ANOTHER FORK IN ROAD, TAKE ROAD BEARING RIGHT PROCEED 0.3 MILES ALONG DIRT ROAD, SET 200 FT. SOUTH OF THE CENTER OF THE DIRT ROAD AT THE SOUTHERLY EDGE OF A PLOWED FIELD AT THE BASE OF A FINGER OF THE RIDGE THAT DIPS INTO THE VALLEY, 2 FT. EAST OF A STEEL WITNESS POST, SET AT THE TOP OF A CONCRETE POST, 0.5 OF A FT. ABOVE THE GROUND, ABOUT 20 FT. HIGHER THAN THE ROAD.

