

GPS #: 1502

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3P-19-68

OCS Index Map: 6LA

Page/Grid: 971/B-1

City / Location: Laguna Beach

Scale Factor: 0.99995865

Ellipsoid Red. Factor: 0.99999972

Combination Factor: 0.99995837

Convergence Angle: -00 49 22.84829

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 22.91382	117 44 51.72616	2131151.101	6105140.259	5.942
2007.00	33 30 22.93083	117 44 51.74226	2131152.84	6105138.92	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3P-19-68", SET IN THE TOP OF A CONCRETE RETAINING WALL. MONUMENT IS LOCATED ALONG THE EASTERLY SIDE OF PACIFIC COAST HIGHWAY, 1.75 MILES NORTHWESTERLY OF THE CENTERLINE OF CROWN VALLEY PARKWAY, ACROSS PCH FROM THE "LAGUNA ROYALE APARTMENTS (#31423 PCH)" AND 43.9 FT. EASTERLY OF THE CENTERLINE OF PCH. MONUMENT IS SET 1.0 FT. ABOVE THE CURB ALONG PCH.

