

GPS #: 1503

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3Z-39-71

OCS Index Map: 6LA

Page/Grid: 951/A-2

City / Location: Laguna Beach

Scale Factor: 0.99996112

Ellipsoid Red. Factor: 0.99995859

Combination Factor: 0.99991972

Convergence Angle: -00 49 37.23253

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 54.18978	117 45 17.90229	2146471.865	6103144.731	865.290
2007.00	33 32 54.20665	117 45 17.91866	2146473.59	6103143.37	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "3Z-39-71". LOCATED AT THE NE PART OF THE INTER OF TEMPLE HILLS DR. AND ALTA LAGUNA BLVD., 55' NW FROM THE CENTERLINE OF TEMPLE HILLS DR., 30.5' NE FROM THE CENTERLINE OF ALTA LAGUNA BLVD., SET AT THE NW CORNER OF A CONC. 5.5' X 5.5' WALL OF AN UNDERGROUND VAULT, LEVEL WITH THE SIDEWALK.

