

GPS #: 1505

Date Destroyed:
Date Revised: 4/23/1996
Benchmark Designation: 3F-96-70
OCS Index Map: 6LA
Page/Grid: 921/A-4
City / Location: Laguna Beach

Scale Factor: 0.99996388
Ellipsoid Red. Factor: 0.99999259
Combination Factor: 0.99995647
Convergence Angle: -00 49 37.23779

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 14.23967	117 45 17.91185	2160626.282	6103348.241	154.885
2007.00	33 35 14.25657	117 45 17.92812	2160628.01	6103346.89	

References: OCS FILE # OC96/7-5, GEODETIC UNIT CR 2000-0045

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "3F-96-70". LOCATED 0.5 MILE NE ALONG EL TORO RD. FROM THE INTER OF LAGUNA CANYON RD., TO THE BEGINNING OF A CURVE CENTERLINE SURVEY MONUMENT, 95.5' SW OF A POWER POLE #1502914E, 32.5' SE OF THE CENTERLINE SURVEY MONUMENT IN CAPPED WELL, 1' NW OF A FENCE, SET AT THE TOP OF A CONC. POST, ABOUT 5' LOWER THAN THE RD. AND 1' ABOVE THE GROUND.

