

**GPS #:** 1510

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation: 3B-84-73

OCS Index Map: 5LB

Page/Grid: 830/B-6

City / Location: Tustin

Scale Factor: 0.99997670

Ellipsoid Red. Factor: 1.00000185

Combination Factor: 0.99997855

Convergence Angle: -00 51 49.87378

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 09.65237	117 49 19.27991	2208976.604	6083656.157	-38.642
2007.00	33 43 09.66894	117 49 19.29663	2208978.30	6083654.77	

References: OCS FILE # OC96/7-5, GEODETIC UNIT

## Description:

DESCRIBED BY OCS 2002 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3B-84-73", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED ALONG THE NORTHEASTERLY SIDE OF EDINGER AVENUE, 140 FT. NORTHEASTERLY OF THE CENTERLINE OF EDINGER AVENUE, 0.37 MILES SOUTHEASTERLY OF THE CENTERLINE OF REDHILL AVENUE AND 22 FT. NORTHEASTERLY OF THE EASTERLY TRACK ALONG THE ATCHINSON TOPEKA SANTA FE RAILROAD. MONUMENT IS SET 0.2 FT. BELOW GROUND

